

**COMPUTER CENTRE**  
**PANJAB UNIVERSITY, CHANDIGARH - 160014.**  
**Website:<http://cc.puchd.ac.in>**

Prof. R. K. Singla  
Director  
Phone 2534077, 4073  
Email: [directorcc@pu.ac.in](mailto:directorcc@pu.ac.in)

No.CC/15/428- 436

Dated: 12-06-2015

---

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Dear Sir,

Kindly quote your rates for the Items/ Works as per specifications enclosed in Annexure-I, to be purchased by the Computer Centre, P.U. Chandigarh.

The quotation in a sealed envelope (mentioning clearly the terms and conditions of payment, rate of Sales Tax applicable etc. and other terms) may please be addressed to **the Director, Computer Centre, Panjab University, Chandigarh 160014** which must reach the office **by 04:00 PM, 25<sup>th</sup> June 2015**, Please attach the relevant literature and full technical specifications of the equipment.

**Terms and conditions for the supply are:**

1. The delivery will be FOR Computer Centre, P.U. Chandigarh.
2. No advance payment will be made.
3. Full and final payment will be made on the receipt of the material and satisfactory installation.
4. P.U. does not issue C or D form.
5. The contract for supply of equipment/ works will be awarded to the firm quoting the lowest total cost for all the items as a whole.
6. Quantum of labour work is on the basis of estimates but the payment will be made on the basis of actual work.

Thanking you,

Yours faithfully

Director

S. No.	Details of Work	Quantity
1	Laying of HDPE duct by Horizontal Directional Digging (HDD) at a depth of 10 Ft. Diameter of HDD should be suitable to accommodate 2 nos. of HDPE ducts of size 40 mm for a length of 1500 meters and 1 no. of HDPE ducts of size 40 mm for a length of 2000 meters.	3,500 M
2	Laying of Fibre in HDPE pipe.	5,000 M
3	Laying of PVC conduit pipe and laying of fibre in conduit pipe with accessories.	100 M
4	Manholes at every 150 M. Size Cubical:1 meters X 1 meters X 1.1 meters depth Cylindrical: 1 meter diameter and 1 meter depth. Sealing of both ends of the manholes by hard rubber bush of suitable size to avoid entry of rodents into the HDPE pipes. Strength: 22.5 mt. Ton	25
5	Mounting of Rack mounted LIU (24 port SC)	3
6	Mounting of Wall mounted LIU (12 port)	1
7	Termination and Splicing of OFC per pair (Single mode fibre) with OTDR testing reports.	150

The vendor has to provide the work completion report on completion of the works which will include the detailed fibre layout map indicating all the terminations and joints.

- \* The contract for supply of equipment/ works will be awarded to the firms quoting the lowest total cost for all the items as a whole.