

**Dr. A. P. J. Abdul Kalam Computer Centre
Panjab University, Chandigarh – 160014**

Prof. Sukhwinder Singh
Director
Ph. 2534073, 2534077
E-mail: directorcc@pu.ac.in

No.CC/18/_____

Dated _____

Dear Sir,

Kindly quote your rates for the items and works for laying of UTP cables as per specifications enclosed as Annexure-I to be procured by the Dr. A.P.J. Abdul Kalam Computer Centre Panjab University Chandigarh.

The quotation should be in a sealed envelope (mentioning clearly the term and conditions of payment, rate of GST applicable etc. and other terms) may please be addressed to **The Director, Dr. A. P. J. Abdul Kalam Computer Centre, P.U., Chandigarh 160014**, which must reach the office by October 08, 2018 till 3:00 PM. Please attach the relevant literature and full technical specifications.

It is proposed to have a three cover system for this Quotation.

1. Technical Proposal is directed to be kept in a single sealed envelope super-scribed with the words "Technical Proposal for Laying of UTP Cable".
2. Commercial Proposal is directed to be kept in a single sealed envelope super-scribed with the words "Commercial Proposal for Laying of UTP Cable".
3. Both the above sealed envelopes are directed to be kept in a single envelope super-scribed with the words "Proposal for Laying of UTP Cable due at **03:00 PM, October 08, 2018** (Not to be opened before time) ".

Terms and conditions:

1. The delivery will be FOR Dr. A. P. J. Abdul Kalam Computer Centre, P.U. Chandigarh.
2. The time duration to complete the works is 30 days from the date of Purchase Order.
3. No advance payment will be made.
4. The Quotation should be submitted along with refundable Earnest Money of Rs. 5,000/- in the form of Demand draft in favor of **The Registrar, PU, Chandigarh. Quotations not accompanied by Earnest Money or incomplete in any respect will be rejected.**
5. In case the order is not executed within the stipulated period, PU will be at liberty to make purchases through other sources, and to forfeit the earnest money of the Supplier.
6. Full and final payment will be made on the receipt of the items.
7. P.U. does not issue C or D form.

Thanking You,

Yours Sincerely,

(Prof. Sukhwinder Singh)

Proposal for Laying of UTP Cable
List of Items

Sr. No.	Item/ Work Details	Quantity
1.	PVC Conduit pipe 25mm Diameter Impact Resistant ISI/ISO Certified	3000 meter
2.	24 Port Cat-6 Patch Panel (Fully Loaded)	2
3.	Cat 6 I/O with single face plate and SMB.	100
4.	Cat 6 UTP Ethernet patch cords (1 Mtr) Conductors: 23 AWG solid bare copper or better. Insulation: Polyethylene. UL/ETL Verified. ANSI/TIA-568-C.2 Individual cable pair separated by Central Cross separator. Meets and exceeds Cat 6 performance standard. Meets standards for PoE applications. RoHS and LSZH Compliant.	200
5.	Laying of UTP with marking, numbering and tagging in conduit with flexible, band, junction box and clamping.	5000 meter
6.	Fixing of rack with Jack panel & switches	3
7.	Fixing & Punching of I/O with SMB.	210

The contract for works will be awarded to the firms quoting the lowest total cost for all the items as a whole.

Quantities of works mentioned above are an estimate of the total work and will be used for comparison of commercial proposals whereas the payment will be made as per actual.